CAPITAL IMPROVEMENTS PROGRAM FY 2005

PROJECT TITLE:	Second Street Force Main	PROJECT NUMBER:	705
LOCATION:	From 2 nd Street Pumping Station to Bembe	Prior Years' Spending/	\$0
	Beach Road in the vicinity of Awald Road	Encumbrances as of	
		03/01/04	
DEPARTMENT:	Public Works		
DIVISION:	Wastewater		

DESCRIPTION:

Replacement of the 65-year-old sewage force main running under Back Creek from the 2nd Street Pumping Station to its discharge point into the gravity sewer on Bembe Beach Road.

JUSTIFICATION:

Should failure occur, this replacement is critical in order to prevent a possible environmental incident in which 4,500,000 gallons of raw sewage could be discharged into the Chesapeake Bay each day if the old pipe line were to fail.

STATUS:

A design study has been completed, with the determination that there is no immediate need for replacement. Concept plans are complete and on file in the event of an emergency.

APPROPRIATION	PRIOR	CURRENT	EVIOC	EN 07	EW 00	EV 00	EV 10	TOTAL
SCHEDULE	YEARS	FY 05	FY 06	FY 07	FY 08	FY 09	FY 10	TOTAL
Land \$								0
Design					60,000			60,000
Construction					875,000			875,000
Inspection					88,000			88,000
Equipment								0
Other					190,000			190,000
Total \$	0	0	0	0	1,213,000	0	0	1,213,000

FUNDING SCHEDULE	PRIOR YEARS	CURRENT FY 05	FY 06	FY 07	FY 08	FY 09	FY 10	TOTAL
Bond Funds \$					1,213,000			1,213,000
Operating Funds								0
Non City Funds								0
Total \$	0	0	0	0	1,213,000	0	0	1,213,000

ESTIMATED FISCAL IMPACT ON OPERATING BUDGET: Some savings in the annual electrical expenses for the 2^{nd} Street Pumping Station will occur due to the reduced pumping head of the new pipe.

CAPITAL IMPROVEMENTS PROGRAM FY 2005

PROJECT TITLE:	Pump Station Replacements	PROJECT NUMBER:	706
LOCATION:	Whiten Court, Bywater Road, and Annapolis	Prior Years' Spending/	\$0
	Roads Pumping Stations	Encumbrances as of	
		03/01/04	
DEPARTMENT:	Public Works		
DIVISION:	Wastewater		

DESCRIPTION:

Total replacement of existing sewage pumping stations with new concrete wet wells and submersible pumps, controlled by variable speed drives.

JUSTIFICATION:

All three stations are pre-fabricate "Tin Can" pumping stations that consist of an underground steel shell containing the pumps and controls to pump the wastewater collected from the neighborhood to the wastewater treatment plant on Edgewood Road. These stations are in excess of 30 years old and the steel containment vessel is at the end of it's design life.

STATUS:

Selection of design services is underway.

APPROPRIATION SCHEDULE	PRIOR YEARS	CURRENT FY 05	FY 06	FY 07	FY 08	FY 09	FY 10	TOTAL
Land \$								0
Design	35,000	35,000		36,000				106,000
Construction	350,000	350,000		360,000				1,060,000
Inspection	20,000	20,000		20,000				60,000
Equipment								0
Other	42,000	42,000		42,000				126,000
Total \$	447,000	447,000	0	458,000	0	0	0	1,352,000

FUNDING SCHEDULE	PRIOR YEARS	CURRENT FY 05	FY 06	FY 07	FY 08	FY 09	FY 10	TOTAL
Bond Funds \$								0
Operating Funds	447,000	447,000		458,000				1,352,000
Non City Funds								0
Total \$	447,000	447,000	0	458,000	0	0	0	1,352,000

ESTIMATED FISCAL IMPACT ON OPERATING BUDGET: Small reduction in operating and maintenance cost associated with more modern and efficient equipment.

CAPITAL IMPROVEMENTS PROGRAM FY 2005

PROJECT TITLE: Sewer Rehabilitation PROJECT NUMBER: 998

LOCATION: City Wide Prior Years' Spending/ \$23,750

Encumbrances as of 03/01/04

DEPARTMENT: Public Works

DIVISION: Wastewater

DESCRIPTION:

A major section of the City's sewer system was constructed in the 1930's and the larger pipe lines were constructed of concrete pipe. Over the past sixty-plus years, the concrete pipe has been deteriorated by the sewer gases and we recently had a 33" sewer line collapse. Due to location and development over and around these sewer lines, slip lining of the existing sewer is the most cost effective repair.

JUSTIFICATION:

TV inspection of approximately 9,000 feet of the suspect concrete pipe has shown varying degrees of pipe failure.

STATUS:

APPROPRIATION SCHEDULE	PRIOR YEARS	CURRENT FY 05	FY 06	FY 07	FY 08	FY 09	FY 10	TOTAL
Land \$								0
Design				80,000	30,000			110,000
Construction				3,550,000	876,930			4,426,930
Inspection				50,000	50,000			100,000
Equipment								0
Other				225,000	78,070			303,070
Total \$	0	0	0	3,905,000	1,035,00	0	0	4,940,000

FUNDING SCHEDULE	PRIOR YEARS	CURRENT FY 05	FY 06	FY 07	FY 08	FY 09	FY 10	TOTAL
Bond Funds \$				3,905,000	1,035,00			4,940,000
Operating Funds								0
Non City Funds								0
Total \$	0	0	0	3,905,000	1,035,00	0	0	4,940,000

ESTIMATED FISCAL IMPACT ON OPERATING BUDGET: When completed, a reduction of inflow and infiltration should be noted and reflect in a reduction of flow at the WWTP.